CSSD

S.N.	Category / Department	Item Description & Specifications	Brand / Model	Qty	Estimated Unit Rate (INR)	GST	TOTAL PRICE
1	Core Sterilization	HPHV Horizontal Steam Sterilizer (Rectangular, 150L - 200L, Double Door OR Singlr Door, PLC/HMI, Built-in Steam Generator)		1			
2	Core Sterilization	Ethylene Oxide (EtO) Gas Sterilizer (Compact 50L - 80L Tabletop/Floor Model with PLC & Printer)		1			
3	Cleaning & Washing	Heavy Duty Ultrasonic Cleaner (30 Litre Tank capacity, digital timer, heater, sweep frequency)		1			
4	Packaging & Sealing	Continuous Rotary Heat Sealing Machine with digital temperature controller & printer		1			
5	SS Furniture	SS-304 Packing & Inspection Table with overhead light/shelf (Size: 1800x800 mm)		2			
6	SS Furniture	SS-304 Heavy Duty Storage Racks (6 shelves, adjustable bullet feet)		4			
7	SS Furniture & Transport	SS-304 Closed Transport Trolley (between CSSD and OT, locking doors, 4 wheels)		2			
8	SS Furniture & Transport	SS-304 Loading Carriage and Transfer Trolley (matching autoclave)		1			

CSSD

S.N.	Category / Department	Item Description & Specifications	Brand / Model	Qty	Estimated Unit Rate (INR)	GST	TOTAL PRICE
9	CSSD Civil & Partition	Clean Room Partition Work (Modular SS/Aluminum framed glass partitions & cleanroom doors)		1			
10	CSSD Storage	SS-304 Wall-mounted Cupboards & Instrument Cabinets		2			
11	Utilities & Plumbing	Dedicated RO(available in hospital) / Water Softener Plant for Autoclave feed + SS Pipeline distribution & traps		1			
12	Utilities & Electrical	Electrical Panel, MCB/ELCB distribution, heavy-duty power points & ceiling cabling for CSSD		1			
13	Exhaust & HVAC	Dedicated Exhaust System & ETO Gas Venting Ductwork with blower		1			
14	Consumables & Testing	Initial Starter Kit: Bowie-Dick test packs, Chemical indicators (Class 5/6), Biologics, ETO cartridges		1			
		TOTAL ESTIMATED STANDARD TURNKEY CSSD PACKAGE					
15	POST WARRANTY AMC						
16	POST WARRANTY CMC						